

15-065-30028-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Glen Rupe,

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name Hobbs Well No. 1

Location NE-SW Sec. 19 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3922

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 2:45PM Day 14 Month 5 Year 1966

The Above well was plugged as follows:

200'--8 5/8" Surface pipe, cement circulated.
3914'--5 1/2" Production casing cemented with 100 Sx. Top perforations
@ 3873'.

Sanded well back to 3860' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" casing and squeezed well with 35 Sx. gel followed with 75 Sx. cement.
Pump-in pressure 250#. FSIP 100#.

(Cementing and mudding operations performed by United Oil Well Cementing)

(Recovered 2931' 5 1/2" production casing)

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Fehale
Well Plugging Supervisor

INVOICED

DATE 5/17/66

INV. NO. 3228-u