

15-065-22692-00-00

98 R

4-060346

10-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,692
N2 S2 NW /4 SEC. 09, 10 S, 24 W
3630 feet from S section line
3960 feet from E section line

Operator license# 3655 Lease Anton Herman well # 3

Operator: Staab Energy & Leasing County Graham 132.93

Address: 2514 Haney Drive Well total depth 4090 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Co., Inc. License# 5665

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:45P.M. Day: 2 Month: October Year: 92

Plugging proposal received from: Burton Berry

Company: Shields Drilling Co., Inc. Phone:

Were: Order 200 sxs. 60/40 pozmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:45A.M., Day: 2, Month: October, Year: 92

Actual plugging report:
1st. plug at 2180' with 25 sxs. - Anhydrite 2163' - 2198'.
2nd. plug at 1290' with 100 sxs. - Dakota 986' - 1286'.
3rd. plug at 275' with 40 sxs. - Surface pipe to 221'.
4th. plug at 40' with 10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Cemented by: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X
Plugged through TUBING , CASING . Elevation: 2511

I did not [X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
10-21-1992
OCT 21 1992
CONSERVATION DIVISION
Wichita, Kansas

[Signature]

(agent) E. a. d.

DATE 10-29-92

INV. NO. 36618