

To: 031338
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,130
NW SW SW, SEC. 17, T 10 S, R 24 W W

TECHNICIAN'S PLUGGING REPORT

Operator License # 3135

990 feet from S section line
4950 feet from E section line

Operator: Crump Pet Corp
Name & Address 710 North Colorado Suite 115
Box 1732
Midland, Texas 79701

Lease Name D. Rush B Well # 3
County Graham 130.00

Well Total Depth 4000 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 174

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number

Address Hill City, Mo.

Company to plug at: Hour: PM Day: 23 Month: Feb Year: 19 90

Plugging proposal received from John

(company name) Murfin (phone)

were: 8 5/8" set at 174' w/cwc sks 4 1/2" set at 3989' w/160 sks. Perf 3725 - 3907.

Order 400 sks 65/35 poz 8% gel 500# hulls. Halliburton Cement Co. Murfin Drilling.
Water Truck. Tubing parted at 1830'. Ran fishing tools, recovered 90' of bad tubing
in area of bad casing. Could not do anymore to well. Decision was to P and A.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00PM Day: 23 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1920' mixed and pumped 200 sks

cement blend to circulate cement to surface. Laid down tubing, loaded displacement

and squeezed 4 1/2" casing w/20 sks. Locked up at 1000#. Max psi, close in psi 800#

with total material of 220 sks w/450# hulls mixed in. Squeezed 8 5/8" annulus w/100sk

cement blend w/50# hulls to max psi 400#. Close in psi 150#. Plug complete.

Remarks: MAR 15 1990
3-15-1990

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 3-16-90

INV. NO. 27689

Carl S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow