

6 070146

API NUMBER 15-065-21, 966-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW-NW-SE, SEC. 15, T. 10 S, R. 24 01N
2310 feet from N(S) section line
2310 feet from N(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6124
Operator: F.T.B. INVESTMENTS
Name & Address: P.O. BOX 366
RUSSELL, KANS.
67665

Lease Name RUDER Well # 1
County GRAHAM
Well Total Depth 3990 129.68 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG #628

Plugging Contractor EMPHASIS OIL OPERATIONS INC. License Number 8241

Address P.O. BOX 506, RUSSELL, KANS. 67665

Company to plug at: Hour: 6:00 AM Day: 4th Month: MAY Year: 19 84

Plugging proposal received from MINE DEENHAM.

(company name) EMPHASIS DRILLING INC. (phone) 913-483-2176

were: 8 5/8 - 255th S.P. OULth / 165th SK COMMON GEL - CA-CL - (BY ALLIED OMT.)

ORDER 195th / 50 POZMIX GEL - CA-CL - 1th SK CELLO FLAKE - AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

NO ARBUCKLE - KC FORMATION, ELV. 2428 - ANH. 2060; NO CIRC PROBLEMS.

Plugging Proposal Received by Mason Schmidt
(TECHNICIAN) 2012

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 AM Day: 4th Month: MAY Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 195th / 50 POZMIX GEL - CA-CL - 1th SK CELLO FLAKE - + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

- 1st PLUG @ 2070 FTth / 25th SK OMT.
- 2nd PLUG @ 1200 FTth / 100th SK OMT - 1th SK CELLO FLAKE.
- 3rd PLUG @ 270 FTth / 50th SK OMT.
- 4th PLUG. ^{SOLID BRIDGE} HULLS - PLUG @ 40 FTth / 10th SK OMT.

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: NO SK IN RAT HOLE (CIRCULATE) (CEMENTED BY ALLIED OMT)
(If additional description is necessary, use BACK of this form.)

DATE 5-17-84 did not observe this plugging.

INV. NO. 1541

Signed Mason Schmidt
(TECHNICIAN) (2012)