

6 030823

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

NENE, SEC. 19, T. 10 S, R 24 WE

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name HOBBS Well # A 2

Operator: STATE OF KANSAS

County GRAHAM

Name & Address FEE FUND / FOR ENERGY

Well Total Depth 3940 feet

RESOURCES OIL & GAS CORP.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CMT CO License Number _____

Address PLAINVILLE KANSAS

Company to plug at: Hour: PM Day: 25 Month: 11 Year: 19 86

Plugging proposal received from CARL GOODROW

(company name) AGENT FOR STATE OF KANSAS KCC CON. DIV. (phone) _____

were: 8 3/8 SET @ 248 w/175SX. 4 1/2 SET @ 3939 PERF 3731-3837 HISTORY

OF WELL SHOWED SQUEEZES BUT NOT WHERE ORDER 255 SX. ATL

65/35 P02 10% GEL 2% DICEL 5 SX. HULLS ALLIED CMT. CO.

JOHN KEITH & WELL BROCK WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 PM Day: 25 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT MIX. & PUMP DOWN 8 3/8 - 4 1/2" ANNULUS 1SX. HULLS

120 SX. ATL CMT. MIX. MAX. PSI 300* CLOSE IN 300*

MIX & PUMP DOWN 4 1/2" CSG 4SX. HULLS - 135SX. ATL CMT. MIX.

MAX. PSI 800* CLOSE IN 800* PLUG COMPLETE

STATE CORPORATION COMMISSION

DEC 17 1986

CONSERVATION DIVISION

Wichita, Kansas

Remarks: AT DON BUTCHERS REQUEST - REFERE TO FILES & WELL HISTORY FOR ZONE PROTECTION
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)