

API NUMBER 15-065-22,754-0000

LEASE NAME Rush

WELL NUMBER 1

990 Ft. from S Section Line

2,310 Ft. from E Section Line

SEC. 19 TWP. 10 RGE. 24 (X) or (W)

COUNTY Graham

Date Well Completed 5-3-95

Plugging Commenced 5-3-95

Plugging Completed 5-4-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Staab Oil Co.

ADDRESS 1607 Hopewall Road, Hays, KS. 67601

PHONE#(913) 625-5013 OPERATORS LICENSE NO. 6037

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-3-95 (date)

by Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,005'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	215'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Spot 25 sax cement @2,105' thru drill pipe. Push bridge plug to 1,210', spot 100 sax cement on plug thru drill pipe. Push plug to 265', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman

(Employee of Operator or Contractor)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack P. Beeman, Sec-Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 95

Ruth Phillips
 Notary Public

My Commission Expires:





Shields


15-005-22754-0000

Russell, Kansas

WELL LOG

Operator: Staab Oil Company
 Well: Rush #1
 Commenced: April 26, 1995
 Completed: May 4, 1995
 Contractor: Shields Drilling Co.

Well Description: NW SW SE
 Sec. 19-10S-24W
 Graham County, Kansas



Elevation: 2,436' KB
 Treatment:
 Production: D & A

CASING RECORD

Size	Run	Pulled
8 5/8"	215'	Cmtd. w/150 sax

Tops:

..... Figures Indicate Bottom of Formations

Post rock	40'
Shale	218'
Shale & sand	1,968'
Shale	2,086'
Anhydrite	2,124'
Shale	3,298'
Shale & Lime	3,620'
Lime	4,005' RTD