

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-22360-0000

LEASE NAME Hobbs "A"

WELL NUMBER 1

SPOT LOCATION SW NE NW

SEC. 19 TWP. 10 RGE. 24 (W)

COUNTY Graham

Date Well Completed 4-19-1987

Plugging Commenced 4-19-1987

Plugging Completed 4-19-1987

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A & A Discovery, Inc.

ADDRESS Box 100 Hill City, Kansas 67642

PHONE # (913) 674-2234 OPERATORS LICENSE NO. 4748

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays Office

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 4430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To  | Size   | Put in | Pulled out |
|-----------|---------|------|-----|--------|--------|------------|
| Surface   |         | 0    | 217 | 8 5/8" | 217    | 0          |
|           |         |      |     |        |        |            |
|           |         |      |     |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug set at 2050' with 20 sacks common cement, 60-40 Poz, 3% Cal Cl 6% Gel;  
2nd. plug set at 1150' with 100 sack common cement, 1 sack cello flake, 60/40 Poz 3% Cal cl 6% Ge  
3rd. plug set at 250' with 40 sacks common cement, 60/40 Poz, 3% Cal cl 6% Gel;  
4th plug set at 40' with 10 sacks common cement, 60/40 Poz, 3% Cal cl. 6% Gel;  
10 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan License No. \_\_\_\_\_  
Address Hays, Ks. 67601


STATE OF Kansas COUNTY OF Graham, ss.

Terry M. Helberg (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
(Signature) Terry M. Helberg

MAY 8 1987 (Address) Box 32 Morland Ks. 67650

SUBSCRIBED AND SWORN TO before me this 21 day of April, 1987  
CONSERVATION DIVISION  
Wichita, Kansas  
Coleen Shields  
Notary Public



My Commission expires: March 11, 1990