

4-032239

5-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-21,446 -0000

E2 NW SW /4 SEC. 24, 10, 24 W
1980 feet from S section line
4290 feet from E section line

Operator license# 30076

Lease: ^{RTKCC} Page ~~(Sprout)~~ Well # 1

Operator: A & A Production

County: Graham 133.25

Address: Box 100
Hill City, Kansas 67642

Well total depth 4100 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 14 Month: May Year: 1997

Plugging proposal received from: Andy

Company: A & A Production Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.
Allied Cement Company.
Order sand and common cement. 6-17-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:00 P.M., Day: 14 Month: May, Year: 1997

Actual plugging report: 8 5/8" set at 265' w/175 sxs cwc. 4 1/2" set at 4099' with 200 sxs. Prod. Perf. 3874'- 3995'. Shots at 1900' - 1600' - 1200' - 900' - 700'. Recovered 700' of 4 1/2". Mixed and pumped down 4 1/2" 160 sxs cement blend with 300# hulls to circulate. Pulled casing. Topped off with 15 sxs. Hole was sanded back to 3800' with 4 sxs common cement on sand with bailer. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

Form CP-2/3

DATE 6-18-97
NO. 48354

(Handwritten mark)