

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20676-00-00  
Spot: W2W2SE Sec/Twnshp/Rge: 24-10S-24W  
1320 feet from S Section Line, 2200 feet from E Section Line  
Lease/Unit Name: PAGE Well Number: 2  
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet: 129.68  
Surface Casing: Size 8.625 feet: 167 150 SX  
Production: Size 4.5 feet: 3989 175 SX  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/12/2002 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 12 sxs gel - 500# hulls.  
Perf casing at 2100' and 1100'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/12/2002 10:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:  
RU Cementers to 8 5/8" S.P. Squeezed 30 sxs cement with 100# hulls.  
Max. P.S.I. 300#.  
RU Cementers to 4 1/2" casing. Squeezed 25 sxs cement with 300# hulls and 12 sxs gel, 150 sxs cement with 100# hulls.  
Max. P.S.I. 800#. S.I.P. 300#.

RECEIVED  
MAY 07 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: CSG

District: 04

Signed Dennis J Hamel  
(TECHNICIAN)

INVOICED

DATE 5-7-02  
WELL NO. 2002061746

Form CP-2/3

APR 26 2002

DON E. PRATT

#2 PAGE

24-10-24W

440' FWL &amp;

BOX 370, HAYS, KS.

CONTR MURFIN DRILLING CO.

CTY GRAHAM

1320' FNL, SE  $\frac{1}{4}$ 

GEOL J. R. GREEN

FIELD DORMAN

E 2385 KB CMP 5/12/74 CARD ISSUED 6/20/74 IP P 152 BOPD + TR WTR

API 15-065-20,676

KC 3798-3832 OA

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |

| LOG  | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| TOP  |      | 3474  | -1089 |
| HEEB |      | 3686  | -1301 |
| TOR  |      | 3708  | -1323 |
| KC   |      | 3722  | -1337 |
| BKC  |      | 3955  | -1570 |
| RTD  |      | 3990  | -1605 |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

- 8-5/8" 167/150SX, 4 1/2" 3989/175SX  
DST (1) 3691-3748/30-30-30-30, REC  
120' GIP, 810' MGCO, BHP 1172-1156#,  
FP 65-349#
- DST (2) 3742-87/30-30-30-30, 1100' GIP,  
REC 2175' GSY 0, BHP 1067-1035#,  
FP 325-918#
- DST (3) 3786-3813/90", 1050' GIP, REC  
1410' GCO, BHP 1017#/30"-1001#/30"  
FP 56-543#
- DST (4) 3812-46/90", 480' GIP, REC  
2060' MDY GCO, BHP 1034#/30"-1018#/  
30", FP 146-953#
- DST (5) 3844-90/30", REC 20'M, FSIP  
390#/30", FP 32-32#
- DST (6) 3873-3932/30-30-30-30, REC  
1230' MDY GCO, BHP 1162-1133#, FP  
105-524# (OVER)