

12-9

4-031883

D-17,639

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,686-000

C SE /4 SEC. 24, 10 S, 24 W
1320 feet from S section line
1320 feet from E section line

Operator license# 30606 Lease Page _____ well # 4

Operator: Murfin Drilling Company, Inc. County Graham

130.65

Address: 250 N. Water Well total depth 4020 feet
Suite 300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 166 feet

Aband. oil well ____, Gas well ____, Input well X, SWD X, D & A ____

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 9 Month: December Year: 93

Plugging proposal received from: John Gerstner - Marion J. Schmidt - KCC

Company: Murfin Drilling Company Phone: _____

Were: Order 400 sxs. 60/40 pozmix - 8% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 9, Month: December, Year: 93

Actual plugging report: 8 5/8" set @ 166' w/150 sxs. cwc. 5 1/2" set @ 4019' w/175 sxs. Production perf. 3791' - 3844'. PBTD 4004'.

Squeezed @ 1200' w/200 sxs. @ 990' w/200 sxs. @ 855' w/200 sxs. @ 825' w/310 sxs. Top squeezed w/50 sxs. Cement in braden head. Squeezed 5 1/2" w/400 sxs. cement blend w/500# hulls mixed in to Max. P.S.I. 300#.
Close in P.S.I. 100#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 27 1993
12-27-93

Remarks: _____

Condition of casing(in hole): GOOD X BAD _____ Any plug: YES X NO _____

Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X NO _____

Plugged through TUBING _____, CASING X. Elevation: _____ GL

I did X did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 12-29-93

INV. NO. 35995 39596

HO

(agent)