

15-065-20687-0000

4-041941

8-25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 6-74

S2 S2 SE /4 SEC. 24 , 10 S, 24 W
330 feet from S section line
1320 feet from E section line

Operator license# 30606

Lease: Page Well # 5

Operator: Murfin Drilling Company, Inc.

County: Graham 130.59

Address: 250 N. Water - #300
Wichita, Kansas 67202

Well total depth 4018 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 170 Feet
W/150 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Murfin Drilling Company License# 30606

Address: Hill City, Kansas 67642

Company to plug at: Hour: 9:00 A.M. Day: 25 Month: August Year 1997

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone: -

Were: 5 1/2" casing set at 4017' w/150 sxs cement.
Perfs at 3926' - 3932'. Anhy at 2030' - Dakota at 1300'.
Ordered 350 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 500# hulls.

11-20-97

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 12:00 P.M., Day: 25, Month: August, Year: 1997

Actual plugging report: Hooked-up to 5 1/2" casing - pumped as follows: 165 sxs 60/40 pozmix with 10% gel in cement. Perf casing at 2030' and 1300' - pumped additional 155 sxs 60/40 pozmix - 10% gel with 450# hulls. Max. P.S.I. 500#. S.I.P. 100#. Pumped down 8 5/8" S.P. with 35 sxs.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: G.L.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did [X] / did not [] observe the plugging.

Dennis Hamel
(agent)

INVOICED
NOV 24 1997

DATE
INV. NO. 49569