

15-065-00008-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kimbark Operating Company,
Complete Address P. O. Box #86, Plainville, Kansas.
Lease Name Vance Well No. 1
Location NW-SW-NE Sec. 5 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 4130'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address P. O. Box #364, Great Bend, Kans. License No. 399
Operation Completed: Hour 3:00 PM Day 29 Month 11 Year 1974

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 160 Sx.
4121'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations from 3903' to 3907'.

Sanded well back to 3850' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 11 sacks gel following with 110 Cu. Ft. cement from 1325' to 1000', then 19 sacks gel from 1000' to 240' and followed with 30 Cu. Ft. cement from 240' to 165' then 3 sacks gel from 165' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-200#. Final Shut-in pressure-75#. (Mudding & cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 390-w