

15-065-20630-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company,

Complete Address 1130 KSB&T Building, Wichita, Kansas.

Lease Name McGuire Well No. C-1

Location SW-NW-SW Sec. 8 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4010'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita, Plaza, Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour 5:00 AM Day 24 Month 10 Year 1973

The above well was plugged as follows:

280'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement  
thru DP from 1050' to 725'. Pulled DP to 285' and displaced 30 Cu. Ft. cement thru  
DP from 285' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/30/73

INV. NO. 8079-10

Signed: W. L. Nichols  
Well Plugging Supervisor