

15-065-20598-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Delta Western Company,  
Complete Address c/o Jim Morris, 211 North Broadway, Wichita, Kansas.  
Lease Name Brungardt Well No. A-1  
Location SW-NE-NE Sec. 8 Twp. 10 Rge. (E) (W) 25  
County Graham Total Depth 4070'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Gabbert-Jones, Incorporated,  
Address 830 Sutton Place, Wichita, Kansas. License No.       
Operation Completed: Hour 9:15 PM Day 15 Month 4 Year 1973

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement  
thru DP from 1250' to 925'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Phelps*  
Well Plugging Supervisor

INVOICED

DATE 4/23/73  
INV. NO. 7264-W