

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-195-20053-00-00

RECEIVED
DEC 8 1967
12-08-1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Beacon Resources Corporation,
Complete Address 412 Union Center, Wichita, Kansas.
Lease Name Hubalek Well No. 1
Location NW-SW-SE Sec. 19 Twp. 12 Rge. (E) (W) 22
County Trego Total Depth 3470
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor L. J. Dreiling and Sons, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 7:00 PM Day 28 Month 11 Year 1967

The above well was plugged as follows:

160'--8 5/8" Surface pipe, cement circulated with 125 Sx.
Dakota section from 1310' to 1535'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru
DP from 1550' to 1230'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar. (Cementing operations by Allied Cementing Co, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. F. Johnson
Well Plugging Supervisor

DATE 12/8/67
INV. NO. 6864-W