

15-195-01085-00-00

RE

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 19 TWP. 12 RGE. 22

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Hubalek

Operator Imperial Oil of Kans, Inc. Address 780 Fourth Nat'l Bldg. Wichita, Kans

Field \_\_\_\_\_ County Grego

Total Depth 4180 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

500', displaced 25 sax cement through drill pipe, heavy mud to

200', set cementing plug and 20 sax cement through drill pipe, heavy

mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement

to bottom cellar.

*Edmond Petty*

District Conservation Agent

Date 10-28-57

RECEIVED

307 31 1237  
10-31-1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 19 T. 12 R. 22W  
BOOK PAGE 38 LINE 15