

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-195-21, 053-00-08

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name JOHN J DARRAH JR.

Complete Address 405 CENTRY PLAZA, WICHITA, KANS. 67202

Lease Name BUNKER Well No. #1

Location NW-NE-SW Sec. 24 Twp. 12 Rge. 22 (East)(West)

County TREGO Total Depth 4100 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MALLARD DRILLING INC. (WAYNE STOUT.)

Address 405 CENTRY PLAZA, WICHITA, KS. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 10:45 AM Day: 30 Month: JULY Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 257 FE SO. CUC. w/ 175 ST COMMON - 2% GEL. - 3% CA-CL. (BY ALLIED)

ORDERED 150 ST 50/50 FORMIX 4% GEL. - 3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1 ST PLUG. @ 910 FE w/ 80 ST CMT.

2 ND PLUG. @ 270 FE. w/ 40 ST CMT.

3 RD PLUG. -> SOLID BRIDGE MUD'S - PLUG. @ 40 FE TO 0 w/ 10 ST CMT.

10 ST IN RHT HOLE. (SPOT)

10 ST IN MOUSE HOLE (SPOT.) CEMENTED BY ALLIED

Amount of Surface Casing: 257 FE

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Murray Schmidt  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
08-02-1982  
ALLI 02 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED  
DATE 8-9-82  
INV. NO. 788 DW

DW