

10-30-87

6 030989

API NUMBER 15-065-01021-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 E/2 NW, SEC. 30, T 10 S, R 24 11W/E

3960 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Lease Name Hanna Well # 1

Operator: Rons Oil Operation

County Graham 133.67

Name & Address

Well Total Depth 4113 feet

Route 1 Box 112

Conductor Pipe: Size _____ feet

Penokee, Kansas 67659

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated OWWO

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ AM Day: 30 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone) _____

were: 8 5/8" set at 245' owc, 5 1/2 set at 4100' w/150 sks. Perf 4021' - 24'

3852' - 54' Sand to 3800'. Order sand and Common Cement. Shoot and pull pipe

Order 200 sks ATL 65/35 Pozmix 10% Gel 2% Dical. Allied Cement Blend.

5 sks Hulls. Water from swab tank.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 30 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3800' w/5 sks Common Cement on sand w/bailer.

6 shots at 3000' 2500' 1800' 1600' 1400' 1200'. Recovered 1200' of 5 1/2" casing

Squeezed 8 5/8" w/100 sks ATL Cement Blend w/5 sks Hulls mixed in to Max Psi

150#. Close in Psi 150#.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1987
11-30-87

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did ~~not~~) observe this plugging.

DATE 12-4-87

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 19136

Carl Goodrow