

15-065-21543-00-00 279
1-31 R

6 031226

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-21,543
SE 34 SEC. 2, T 10 S, R 25 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5453
Operator: L K Wireline Inc.
Name & Address: Box 1188
Hays, Ks. 67601

Lease Name Rome Well # 1
County Graham 141.28
Well Total Depth 4347 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____
Address Russell, Ks.

Company to plug at: Hour: _____ PM Day: 31 Month: Jan Year: 19 89

Plugging proposal received from Bill Longpine
(company name) L K Wireline (phone) _____

were: 8 5/8" set at 257' w/200 sks 5 1/2" set at 4330' w/200 sks.
Perfs 3911' - 18'. Shots anhy at 2114' and Kiowa at 1400'. Order 300 sks 65/35 Poz 10% Gel
2% Dicol 500# Hulls. Allied Cement Co. Rush Water Trucks.

Fluid level at 3000+;

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:45PM Day: 31 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/175 sks cement w/400# Hulls.

Mixed into max psi 600#. Close in psi 600#. Squeezed 8 5/8" w/125 sks to max psi 300#.

Close in psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
2-7-1989
FEB 7 1989

Remarks: (if additional description is necessary, use BACK of this form)
Conservation Division
Wichita, Kansas

INVOICED observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

DATE 2-8-89
INV. NO. 23888

1-31 MAY 16 1989