

10-715-065-21679-0000

4-041520

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-

SW NE SW /4 SEC. 36 10 S, 24 W
1650 feet from S section line
3630 feet from E section line

Operator license# 6931 Lease Ruder well # 1

Operator: Bowman Oil Company County Graham

Address: P.O. Box 37
Codell, Kansas 67630
Well total depth 3960 feet *(4250)*
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 242 feet
w/175 sxs. *128.70*

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 7 Month: October Year: 93

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone:

Were: 4 1/2" casing set @ 3960' w/100 sxs. cement. Perf. @ 3718'-3724'.
Anhy. @ 1945' - Dakota @ 800' - W.L.M. 3550' - C.I.B.P. 3738' and 3820'
plus 8 sxs. gel. Ordered 225 sxs. 60/40 pozmix - 10% gel. with 1/4#
F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 7, Month: October, Year: 93

Actual plugging report: Spot @ 2000'. 125 sxs. cement with 200# hulls
and 50 sxs. cement. Squeezed 8 5/8" with 350 sxs. cement and 100# hulls.
Squeezed casing with 60 sxs. additional cement. Max. 600#. S.I. 400#.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation:

I did X / did not [] observe the plugging.

INVOICED
DATE 10-21-93
INV. NO. 39001
10-7

Dennis L. Hamel
(agent)
RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1993
CONSERVATION DIVISION
Form CP-21
Wichita, Kansas