

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21510-00-00  
Spot: CNWNENW Sec/Twnshp/Rge: 35-10S-24W  
330 feet from N Section Line, 1660 feet from W Section Line  
Lease/Unit Name: GEYER Well Number: 2-35  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4038 150 SX CMT ~~131.30~~  
Surface Casing Size: 8.625 feet: 238 210 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/19/2003 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perf casing at 900' and 2060'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/19/2003 11:40 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing 2016' - spotted 85 sxs cement with 400# hulls.  
Pulled to 1013' - spotted 45 sxs cement with 200# hulls.  
POOH with tubing - squeezed 4 1/2" casing with 40 sxs cement.  
Max. P.S.I. 400#. S.I.P. 100#.  
Rigged up to 8 5/8" S.P. - squeezed 35 sxs cement with 500# hulls.  
Max. P.S.I. 200# S.I.P. 500#.

RECEIVED  
MAR 20 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 3-20-03

INV. NO. 2003061316

Form CP-2/3

MAR 11 2003

replacement card

MURFIN DRILLING CO  
WICHITA KS

35-10S-24W  
NW NE NW

# 2-35 GEYER

site: 2-3/4 S & 5-3/4 E OF ST PETER KS

ty: GRAHAM

API 15-065-21510

contr: MURFIN DRILLING

field: GEYER

geol:

lr  
date 10/01/81

spd  
date 09/30/81

drig  
comp 10/09/81

card  
issued 12/02/82

last  
revised 05/12/97


ELV: 2410 KB, 2405 GL LOG  
tops.....depth/datum  
ANH.....2032 + 378  
B/ANH.....2066 + 344  
NEVA.....3041 -631  
TOP.....3505 -1095  
HEEB.....3726 -1316  
TOR.....3747 -1337  
LANS.....3761 -1351  
BKC.....3998 -1588  
LTD.....4040 -1630  
RTD.....4040 -1630

**IP status:**

**OIL, P 22 BO & 118 BWPD, LKC 3900-3987 OA, 11/24/81**  
INFO RELEASED: 5/12/97 - WAS OIL WELL - TIGHT HOLE  
CSG: 8-5/8" 238 / 210 SX, 4-1/2" 4038 / 150 SX  
NO CORES  
DST (1) 3723-3810 (SHAW, LKC), / 45-45-45-45, REC 70'  
M ISIP 1178# FSIP 1124# IFP 76# -86# FFP 97# -108#  
IHP 2111# FHP 2089#  
DST (2) 3824-3842 (LKC), / 30-45-30-45, REC 10' M  
ISIP 97# FSIP 43# IFP 32# -32# FFP 32# -32# IHP 2100#  
FHP 2079# BHT 114'

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)