

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21511-00-00
Spot: ^{N2}~~CN~~W^{RTWCC}NWNW Sec/Twnshp/Rge: 35-10S-24W
330 feet from N Section Line, 660 feet from W Section Line
Lease/Unit Name: GEYER Well Number: 3-35
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4049 150 SX CMT ^{8131.63}
Surface Casing Size: 8.625 feet: 209 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2003 2:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perf casing at 900' and 2060'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/19/2003 4:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing 2131' - spotted 85 sxs with 400# hulls.
Pulled tubing to 1019' - mixed 55 sxs cement with 150# hulls - circulated cement.
POOH with tubing and squeezed an additional 35 sxs cement.
Max. P.S.I. 250#. S.I.P. 200#.
Rigged up to 8 5/8" S.P. and squeezed 55 sxs cement with 50# hulls.

RECEIVED
MAR 20 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed: Dennis J. Hamel
(TECHNICIAN)

INVOICED

DATE 3-20-03

INV. NO. 2003061316

Form CP-2/3

MAR 11 2003

MURFIN DRILLING CO
617 UNION CENTER

#3-35 GEYER

35-10-24W
NW NW NW

WICHITA, KS 67202

CONTR MURFIN DRILLING CO

CTY GRAHAM

GEOL

FIELD GEYER

E 2410 KB CM 10/9/81 CARD ISSUED 3/11/82 IP P 7 B0 & 140 BWPD

2405 GL

LANS 3838-3988 OA

API 15-065-21,511

0	+	+	+
-	+	+	-
-	-	-	-
-	-	-	-

LOG TOPS	DEPTH	DATUM
ANH	2037	+ 373
B/ANH	2072	+ 338
TOP	3507	-1097
HEEB	3727	-1317
TOR	3750	-1340
LANS	3764	-1354
B/KC	4000	-1590
LTD	4047	-1637
RTD	4050	-1640

8 5/8" 209/185sx; 4 1/2" 4049/150sx

DST (1) 3822-46(LKC)/45-60-45-60, REC
117' OCM, SIP 394-383#, FP 41-

72#
DST (2) 3881-3934(LKC)/30-30-30-30,
REC 104'M, SIP 1175-1126#, FP

49-49/68-68#
DST (3) 3930-55(LKC)/45-60-45-90,
REC 20'SL O & GCMW, 240'SGMW,
SIP 1340-1321#, FP 29-137#

DST (4) 3953-92(LKC)/TIMES NA, REC
60'M, SIP 1081-1010#, FP 51-

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS