

6 030710

15-0005-21791-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE, SEC. 35, T 10 S, R 24

900 feet from S section line

600 feet from E section line

Lease Name LICHTSINN Well # 1-35

County GRAHAM 137.22

Well Total Depth 4222 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216'

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Operator: MURFIN DRUG. Co.

Name & Address Box 130

HILL CITY KANSAS

67642

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 17 Month: 4 Year: 19 86

Plugging proposal received from PAT CANADAY

(company name) MURFIN DRUG. (phone) _____

were: 8 5/8 @ 216' w/1154 4 1/2 @ 4222' w/200 SX. PBD 4179 PERF 3798-3800

ORDER 500 SX. ECONOLITE HLC 2 SX. HULLS HALLIBURTON CMT. CO.

WELLBROCK WATER TRUCK.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1986

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6 PM Day: 17 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT LAYDOWN RODS & Pump. MIX. & Pump THROUGH

TUBING 8bbl (16 SX.) ECONOLITE HLC FROM 4179' TO 3700'

LAYDOWN TUBING - PULL STRETCH ON CASING. NOT ENOUGH TO RECOVER

SWABBED HOLE DRY 3500' TO SURFACE LOADED HOLE OPEN END

WITH 70 BBL CEMENT SLURRY (140 SX) HOOK ON TO BACKSIDE MIX & PUMP

30 BBL CMT. SLURRY (60 SX. CMT) MAX. PSI 400# CLOSE IN 300# PLUG. COMP.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

DATE APR 29 1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13592

4-17