

4-031837

6-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,123-00-00

NE NW SE /4 SEC. 11, 12 S, 22 W
2310 feet from S section line
1650 feet from E section line

Operator license# 5886 Lease Adams well # 3
Operator: Chief Drilling, Inc. County Trego

Address: 120 S. Market Well total depth 4075 feet 132.43
Suite #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 242 feet

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Chief Drilling, Inc. License# 5886

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 20 Month: June Year: 93

Plugging proposal received from: Harold

Company: Chief Drilling, Inc. Phone: -

Were: Order 225 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.
Allied Cement Company.
Condition hole before plugging.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:30 P.M., Day: 20, Month: June, Year: 93

Actual plugging report: Spot and displace plugs with drill pipe.
1st. plug with 25 sx. @ 1800'.
2nd. plug with 100 sx. @ 1430'.
3rd. plug with 40 sx. @ 210'.
4th. plug with 10 sx. @ 40'.
Circulate 15 sx. in rathole.
Circulate 10 sx. in mousehole.

Remarks: Anhy. 1792' - 1846' - Marmaton
Condition of casing(in hole): GOOD ____, BAD ____, Anhy. plug: YES ____, NO ____,
Bottom plug(in place): YES ____, CALC ____, NO ____, Dakota plug: YES ____, NO ____,
Plugged through TUBING ____, CASING ____. Elevation: 2334 GL

I did/did not [X] observe the plugging.

Carl Goodrow (agent)
DK
RECEIVED STATE CORPORATION COMMISSION
08-02-1993
AUG - 2 1993

INVOICED
DATE AUG 03 1993
NO. 38234