

6 070329

API NUMBER 15-195-21, 674-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE-SE-NW, SEC. 22, T 12 S, R 22 @18

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name RIDGWAY Well # 1

Operator Name & Address LIBERTY OPERATIONS AND

County TREGO 134.88

COMPLETIONS, INC. 308

Well Total Depth 4150 feet

WEST MILL

Conductor Pipe: Size 0 feet

PLAINVILLE, MANS. 67663

Surface Casing: Size 8 5/8 feet 274 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated TAG # 256

Plugging Contractor PIONEER DRILLING CO. INC License Number 5665

Address PLAINVILLE, MANS. 67663

Company to plug at: Hour: 11:00 AM Day: 10th Month: MARCH Year: 19 85

Plugging proposal received from TOM ALUM

(company name) PIONEER DRILLING CO. INC. (phone) 913-424-4686

were: 8 5/8" - 274' ESP. CUL #1/50 SK #1/40 FORMIX GEL - GA-CL - BY SUN CNT.

ORDER 210 SK 50/50 FORMIX GEL - GA-CL - 1 SK CELLO FLAME AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - RECONDITION HOLE (45") HEAVY MUD BETWEEN ALL PLUGS

NO CIRCULATION PROBLEMS, ARBUCKLE @ 4096', MUD 46 VAS, WEIGHT 10, CH/28000

FLV. 2390, ANH. 1818 FT

Plugging Proposal Received by Marion Schmidt
(TECHNICIAN) 00K

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00 AM Day: 10th Month: MARCH Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 210 SK 50/50 FORMIX GEL - GA-CL - 1 SK CELLO FLAME AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 4080 FT #1/25 SK CNT, 2nd PLUG @ 1830 FT #1/25 SK CNT

3rd PLUG @ 990 FT #1/100 SK CNT #1/2 SK CELLO FLAME, 4th PLUG @ 280 FT #1/40 SK CNT

5th PLUG ^{200 TERRIBLE} HULLS - PLUG @ 40 FT #0 #1/10 SK CNT, 10 SK IN RAT HOLE (CIRCULATE)

CEMENTED BY ALLIED CNT.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-19-85

INV. NO. 7393

MAR 18 1985
03-18-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Marion Schmidt
(TECHNICIAN) 00K

3-15-85
12
FORM CP-273
Rev. 01-84