

4-031628

12-4

218 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,097-00-00

SE NW SE /4 SEC. 24, 12 S, 22 W
1650 feet from S section line
1650 feet from E section line

Operator license# 30676

Lease Sherfick South well #24-66

Operator: Pioneer Oil & Gas

County Trego

Address: 6925 Union Park Center
Suite 145
Midvale, Utah 84047

Well total depth 4100 feet ^{133.25}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet
cwc. 170 sx.

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling License# 6033

Address: 250 N. Water, #300, Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 4 Month: December Year: 91

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling Phone:

Were: Order 225 sx. 60/40 poz. - 6% gel. - 3% c.c. - 8 5/8" W.P.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:45A.M., Day: 4, Month: December, Year: 91

Actual plugging report: Condition well bore with heavy mud.

Balance plugs with mud.

Spot plugs with drill pipe. Spot 25 sx. @ 4100'. - 25 sx. @ 1800'.

100 sx. @ 950' w/hulls.

40 sx. @ 300'.

10 sx. @ 40' W.P.

Circulate 15 sx. in Rathole with joint of pipe.

Circulate 10 sx. in Mousehole with joint of pipe.

Remarks: Anhy. 1780' - 1820' - Arbuckle 4100' - Elev. 2343'.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1991

12-30-1991

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

I did / did not observe the plugging.

Carl Goodrow

DATE 1-10-92

INV. NO. 34310

Rich. S.

(agent)