

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-065-21,617-0000

LEASE NAME Brungardt

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER #1-5

SPOT LOCATION 100' SE of SE-NW-SE

LEASE OPERATOR Pardners Investment Properties Corp.

SEC. 5 TWP. 10 RGE. 25 (E)OR(W)

ADDRESS 2705 Vine Street #8, Hays, Kansas 67601

COUNTY Graham

PHONE #(913) 628-1761 OPERATORS LICENSE NO. 6346

DATE WELL COMPLETED 7/82

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 12/20/82

PLUGGING COMPLETED 12/23/82

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Office #6 1014 Cody Hays, Kansas 67601

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Lansing DEPTH TO TOP 3861 BOTTOM 4094 T.D. 4125

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing	60/40 poz	0	227	8 5/8	227	0
Production Casing	50/50 poz	0	4125	4 1/2	4125	3298
	[2% gel, 10% salt]					

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. See attached copy

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Barlow Well Service LICENSE No. 6690
ADDRESS Box 435 Eads, CO

STATE OF Kansas COUNTY OF Rooks SS.

Paul A. Montoya (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Paul A. Montoya

(ADDRESS) 305 E. 24th Hays, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3rd DAY OF Sept., 1983

Irene Fellhoelter
State Notary Public
Rooks County, Kansas

Irene Fellhoelter
NOTARY PUBLIC

MY COMMISSION EXPIRES: My Commission Expires 4-4-89

RECEIVED STATE CORPORATION COMMISSION FORM CP-4 REVISED 06-83

SEP - 8 1983

CONSERVATION DIVISION
Wichita, Kansas

FELLHOELTER CONSULTING & ENGINEERING

P. O. BOX 86

PLAINVILLE, KANSAS 67663

Company Partners Investment Prop. Corp.

Invoice No. 201

Address 2705 Vine Suite 8

Date December 26, 1982

City Hays, Kansas 67601

Lease Brungardt #1-5

12-16-82 Pumped 50 sacks of 50-50 posmix cement w/6% gel and 2% CC.
Pumped cement w/rubber plug to 3370'. Plug floated to 3495'.
Shut well in.

12-18-82 Barlo Well Service pulled casing 3298'.

12-23-82 Sun Cementing Company plugged well w/170 sacks of 50-50 posmix cement
w/6% gel and 3% CC and 60 sacks of gel and 2 sacks of hulls as follows:

- Mix 42 sacks gel 2 hulls
- Mix 100 sacks cement
- Mix 18 sacks gel
- Mix 70 sacks cement

Well plugged @ 2:45 P.M. December 23, 1982.
State Plugger - Carl Goodrow, Morland, Kansas

3 days	\$350.00
Mileage (267 miles @ 50¢)	133.50

TOTAL INVOICE	\$483.50
---------------	----------

THANK YOU

Pd 1-11-83
ck # 1175

RECEIVED
STATE CORPORATION COMM

SEP - 8 1983

CONSERVATION DIVISION
Wichita, Kansas