

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,409-0000

LEASE NAME Rush ET

WELL NUMBER 1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 8 TWP. 10 RGE 25 XXXXXX(W)

COUNTY Graham

Date Well Completed 9-24-87

Plugging Commenced 9-24-87

Plugging Completed 9-24-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS Rt. 1, Box 183-B; Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District 6 - Hays

Is ACO-1 filed? will be by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plug #1 set at 2180' with 25 sacks cement through drill pipe.

Plug #2 set at 1300' with 100 sacks cement through drill pipe; 1 sack seal flake

Plug #3 set at 350' with 40 sacks cement through drill pipe

Bridge & Plug set at 40' with 10 sacks cement; 15 sacks in rat hole; 10 sacks water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address PO Box 877, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

Ervin Neighbors

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors


(Address) PO Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 30 day of September, 19 87

Dorothy M Hague
Notary Public

My Commission Expires: 5-5-90

STATE CORPORATION COMMISSION



OCT 2 1987

Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS WELL LOG

DATE COMMENCED: September 18, 1987
DATE COMPLETED: September 24, 1987

Davis Petroleum, Inc.
Rush ET #1
SW NW SE
Sec. 8, T10S, R25W
Graham County, KS.

0 - 2170' Surface Soil, Sand, Shale
2170 - 2210' Anhydrite
2210 - 2175' Shale, Lime
2175 - 2179' Shale
2179 - 3832' Lime, Shale
3832 - 4065' Lime
4065 - 4073' Shale, Lime
4073' RTD

ELEVATION: 2553'

FORMATION DATA:

Anhydrite 2170-2210'
Heebner 2175'
Toronto 3816'
Kansas City 3832'
Base K.C. 4065'
RTD 4073'

Surface Pipe: Set new
8-5/8", 20# @ 201' with
180 sacks 60/40 pozmix,
2% gel, 3% c.c.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON)ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 30 day of September, 1987.

Dorothy M. Hague
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1987

CONSERVATION DIVISION
Wichita, Kansas