


15-065-00487-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

GRAHAM County. Sec. 8 Twp. 10 Rge. (E) 25(W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner THE KIMBARK COMPANY
Lease Name MCGUIRE Well No. 1
Office Address P. O. Box 1557, DENVER 1, COLO.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 8/11 1958
Application for plugging filed VERBAL 8/11/ 1958
Application for plugging approved " 8/11 1958
Plugging commenced 8/11 1958
Plugging completed 8/11 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4095 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	202'	8-5/8"	195'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE WITH 25 SX CEMENT AT 600' AND 15 SACKS CEMENT AT 200' AND 10 SACKS CEMENT AT 40'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LOGAN DRILLING COMPANY
Address P. O. Box 1557, DENVER 1, COLORADO

STATE OF COLORADO, COUNTY OF DENVER, ss.
W. K. ARBUCKLE (employee of owner) ~~not a resident of this state~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. K. Ar buckle

P. O. Box 1557, DENVER, COLORADO
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of AUGUST 1958

My Commission expires August 20, 1960

My commission expires _____



PLUGGING
FILE SEC 8 T10 R 25W
BOOK PAGE 123 LINE 38

AUG 27 1958
8-27-58
CONSERVATION DIVISION
Wichita, Kansas

McGUIRE #1 WELL LOG

LOCATION: SE SE NW SECTION 8
T-10-S, R-25-W
GRAMM COUNTY, KANSAS

SPUDED: 8/2/58
COMPLETED: 8/11/58

OWNER: THE KIMBARK COMPANY
P. O. Box 1557
DENVER 1, COLORADO

CONTRACTOR: LOGAN DRILLING COMPANY
P. O. Box 1557
DENVER 1, COLORADO

SURFACE CASING: 8-5/8" SS CASING CEMENTED AT 202' W/125 BAGGS.

OIL STRING: NONE

LOG

FIGURES INDICATE BOTTOM OF FORMATION

207	SAND AND SHALE
1240	SHALE AND SAND
1665	SHALE AND SAND
2005	SAND AND RED BED
2197	RED BED
2225	ANHYDRITE, SHALE AND SAND
2238	ANHYDRITE
2450	SHALE
2630	SHALE AND LIME
2810	LIME AND SHALE
2950	SHALE AND LIME
3086	LIME AND SHALE
3200	LIME AND SHALE
3300	SHALE AND LIME
3370	LIME AND SHALE
3525	LIME AND SHALE
3650	SHALE AND LIME
3767	LIME AND SHALE
3845	LIME
3880	SHALE AND LIME
3930	LIME
3985	LIME
4020	LIME
4075	LIME AND SHALE
4095	LIME
4095	ROTARY TOTAL DEPTH

THE UNDERSIGNED, WALTER K. ARBUCKLE, PRESIDENT OF THE LOGAN DRILLING COMPANY, HEREBY CERTIFIES THAT THE ABOVE IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN DRILLING THE McGUIRE #1 AS SHOWN IN THE DAILY DRILLING REPORTS.

LOGAN DRILLING COMPANY

Walter K. Arbuckle
WALTER K. ARBUCKLE
PRESIDENT

STATE OF COLORADO |

CITY & COUNTY OF DENVER |

BE IT REMEMBERED, THAT ON THIS 22ND DAY OF AUGUST A.D. 1958, BEFORE ME *Cordell Lewis*, A NOTARY PUBLIC PERSONALLY APPEARED WALTER K. ARBUCKLE, PRESIDENT OF LOGAN DRILLING COMPANY, A COLORADO CORPORATION, WHO IS PERSONALLY KNOWN TO ME AND KNOWN TO ME TO BE THE PRESIDENT OF SAID CORPORATION, AND THE SAME PERSON WHO EXECUTED THE FOREGOING INSTRUMENT AND HE DULY ACKNOWLEDGED THE EXECUTION OF THE SAME FOR AND ON BEHALF OF AND AS THE ACT AND DEED OF SAID CORPORATION.

WITNESS MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES My Commission expires August 20, 1960

Cordell Lewis
NOTARY PUBLIC

PLUGGING	
FILE	SEC 8 T. 10 R. 25W
BOOK	PAGE 123 LINE 38

AUG 22 1958
COMMERCIAL BANK