

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

TREGO County. Sec. 18 Twp. 12 Rge. 22 ~~W~~ (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner PETROLEUM, INC.

Lease Name MARQUISS Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 6, 19 57

Application for plugging filed September 7, 19 57

Application for plugging approved September 6, 19 57

Plugging commenced September 6, 19 57

Plugging completed September 7, 19 57

Reason for abandonment of well or producing formation

No Producing Zones

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Box 326, Hays, Kansas

Producing formation ----- Depth to top ---- Bottom ---- Total Depth of Well 4176 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 600' followed by wooden plug. Placed 30 sacks cement through drill pipe on to plug. Mud up to 220' followed by wooden plug. Placed 30 sacks cement through drill pipe on to plug. Mud up to 35' and placed 1/4 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September 19 57
J. D. Brown
Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC 18 T 12 R 22W
BOOK PAGE 42 LINE 44

09-21-1957
DIVISION
KANSAS

WELL LOG

15-195-00283-00-00

COMPANY PETROLEUM, INCORPORATED

SEC. 18 T. 12S R. 22W

FARM MARQUISS NO. 1


LOC. SW, NW, NW

TOTAL DEPTH 4176'

COUNTY Trego Co., Kansas

COMM. August 27, 1957 COMP. September 7, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 249' W/175 sax.

ELEVATION 2414' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

125	Sand & shale
250	Shale
980	Shale & streaks sand
1175	Sand & streaks pyrite
1715	Shale & red bed
1835	Shale & shells
1865	Anhydrite
2020	Shale & shells
2380	Shale & streaks anhydrite
3586	Lime & shale
3968	Lime
4050	Lime & chert
4060	Lime
4108	Lime & chert
4170	Cherty conglomerate
4176	Arbuckle
4176	T. D.

PLUGGING
 FILE SEC. 18 T. 12 R. 22W
 BOOK PAGE 42 LINE 44

STAMP
 09-21-1957
 COMMISSIONER OF GEOL. & MINES
 Wichita, Kansas

State of KANSAS }
 County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Marquiss well

Verne A. Morris

Subscribed and sworn to before me this 19th day of September 19 57

My Commission Expires: July 11, 1960

Delbert Brown
 NOTARY PUBLIC