

15-195-01445-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 1108-22

LOCATION SW NE SW

SEC. 25 TWP. 12 RGE. 22

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Powers \_\_\_\_\_

Operator J. O. Forbes Address Great Bend, Kans

Field Ogallah County Trego

Total Depth 4047 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 362' circulated with cement - 5 1/2" at ~~36~~ 4039'

with 150 sax cement behind.

Set chat to 4030' and 4 sax cement run with dump bailer, pulled

2972' 5 1/2", filled with mud to 330', set rock and 15 sax cement,

mud to 33', set rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
07-06-55  
WICHITA, KANSAS

District Conservation Agent

Date 6-29-55

**PLUGGING**  
CONSERVATION DIVISION  
WICHITA, KANSAS  
FILE SEC 25 T 12 R 22  
BOOK PAGE 108 LINE 22