

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name M. Dinkel Well No. 1

Location NW-NW-SW Sec. 15 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4205'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 1:00 PM Day 5 Month 10 Year 1965

The Above well was plugged as follows:

195'--8 5/8" Surface casing, cement circulated with 200 Sx.
3975'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to
3964'. Top perforations @ 3734'.

Sanded well back to 3700' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with 16 sacks gel plus 5 sacks hulls in initial gel then 100 Sx.

cement from 1175' to 850' then 16 sacks gel from 850' to 210' and followed with 20 Sx.

cement from 210' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement

from 30' to bottom of cellar. Maximum pump-in pressure-700#. Final shut@in Pressure-

-300#. (Mudding and cementing operations performed by Halliburton). Rec. 1034' 5 1/2" Csg.).

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: N. L. Nichols
Well Plugging Supervisor

OCT 8 - 1968

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10/8/68

INV. NO. 858-4