

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-195-00857-00-00

Operator's Full Name Pan American Petroleum Corporation,

Complete Address P. O. Box #432, Liberal, Kansas.

Lease Name R. M. Anderson, Well No. C-1

Location NE-NE-NE Sec. 34 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 4065'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Halliburton Services,

Address Hays, Kansas. License No. _____

Operation Completed: Hour 6:00 PM Day 23 Month 7 Year 1969

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.
4064'--5 1/2" Production casing cemented on bottom with 300 Sx. DV tool set @ 1761' with
800 Sx. cement circulated. Bridge plug @ 3978'. Top perforations @ 3588'. Well plugged
back to 3910'.

Ran tubing to bottom and displaced 75 Sx. cement from 3910' to 3500'. Pulled tubing to
3500' and displaced 35 sacks gel from 3500' to 900'. Pulled tubing to 900' and displac-
ed 50 Sx. cement from 900' to 500'. Pulled tubing to 500' and displaced 6 sacks gel
from 500' to 50'. Pulled tubing to 50' and circulated cement with 5 sacks to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichol
Well Plugging Supervisor

DATE 7/28/69
INV. NO. 168-W