



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Herman Geo. Kaiser

Complete Address 4120 East 51st St. Tulsa, Oklahoma 74135

Lease Name Deane Well No. 4

Location C S/2 NW NE Sec. 14 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3481'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12:05 P Day 30 Month 12 Year 1974

The above well was plugged as follows:

- Total Depth 3481' 8 5/8 csg set at 1158' cwc ~~250~~ sk .
- 4 1/2 csg set at 3478' cw 250 sk cem.
- Filled 4 1/2 csg with sd (3481-3450) dumped 3 sk cmt W/dump bailer. (3450-3420)
- Cutoff & recovered 2310' of 5 1/2 csg.
- Filled 8 5/8 csg W/mud to 375' -set rock & sand bridge (375-350)
- Filled with RM cem. from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 1/6/75
INV. NO. 578-W