


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 15-39  
LOCATION NW NW SW  
SEC. 11 TWP. 10 RGE. 25

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Pfeifer

Operator Empire Drg Co Address 400 Brown Bldg Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 4235 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" 227' circulated with cement - 5 1/2" 3989' with 125 sax  
cement behind - P.B. 3804', perforations 3784.

Filled with sand to 3765', set 4 sax cement with dump bailer, pulled  
3271' 5 1/2" - stopped 5 1/2" at 800', circulated hole with heavy mud  
at 800', displaced 35 sax cement through 5 1/2" at 800', heavy mud  
to 50', set rock and 15 sax cement to bottom cellar.

Mudding and Cementing by Halliburton Cementing Co.

*Leson Pesty*  
District Conservation Agent

Date 6-3-57

RECEIVED  
STATE CORPORATION COMMISSION  
6-7-1957  
JUN 7 1957

PLUGGING  
FILE SEC 11 T 10 25W  
BOOK PAGE 15 LINE 39

CONSERVATION DIVISION  
Wichita, Kansas