

\$ 44.62

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20460-00-00  
Spot: S2SW Sec/Twnshp/Rge: 5-19S-7W  
653 feet from S Section Line, 3924 feet from E Section Line  
Lease Name: ELLIS Well #: 1  
County: RICE Total Vertical Depth: 1373 feet

Operator License No.: 34163  
Op Name: GAS CHASERS INC.  
Address: PO BOX 533  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		
PROD	4.5	1373		75 SXS

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2010 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN STRUBE Company: GAS CHASERS INC Phone: (316) 706-2665

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/26/2010 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE @ 700' AND 250'. RUN TUBING TO 1190' AND PUMP 25 SX'S CEMENT WITH CALCIUM CHLORIDES @ 450#S. PULL TUBING TO 700' AND PUMP 35 SX'S CEMENT--HAD CIRCULATION. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON CASING AND GOT CEMENT RETURNS UP THE BACKSIDE OF CASING ALSO. PULL OUT TUBING AND TOP OFF. USED 155 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
1150	1196	CSG	

INVOICED  
DATE 2/25/10  
INV. NO. 2010060789

RECEIVED  
FEB 05 2010  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. TICKET #5953. COPELAND TICKET C-35827.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

JK