

\$104.07

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20259-00-02
Spot: SENWNW Sec/Twnshp/Rge: 12-26S-2E
4409 feet from S Section Line, 4052 feet from E Section Line
Lease Name: HLADIK Well #: 1
County: SEDGWICK Total Vertical Depth: 3202 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 532 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
T1	2.875	2796		
PROD	5.5	3202	1561	
STRL	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2009 12:00 PM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Rcvd. from: TOM SCHMIDT Company: BEN GILES Phone: (316) 265-1992

Proposed Plugging Method: SAND & CAP ALL PERFORATIONS W/5 SXS, MIDDLE PLUG - IATAN LIME - 35 SXS @ 2010'. CIRCULATE CEMENT 250' TO SURFACE

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2009 12:00 PM KCC Agent: DAVID BOLLENBACK

Actual Plugging Report:

SAND UP & CAP W/5 SXS THE PERFORATIONS @ 3136-3138 (HUNTON) SET CAST IRON BRIDGE PLUG @ 2799 OVER PERFORATIONS @ 2825-28 (MISS). CAP W/5 SXS CEMENT. CUT PRODUCTION CASING @ 1561'. (5 1/2") SET MIDDLE PLUG @ 1561 USED 40 SXS ~~THRU~~ PRODUCTION CASING. PULL 5 1/2 & CIRCULATE CEMENT @ 251' TO SURFACE. 1/11/2010 TOP OFF W/CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3136	3138		HUNTON
2825	2828		MISS

INVOICED
DATE 2/25/10
INV. NO. 2010060791

RECEIVED
JAN 19 2010
KCC WICHITA

Remarks: CEMENT TICKET #34425, COPELAND CEMENT

\$34419

Plugged through: CSG

District: 02

Signed

[Signature]
(TECHNICIAN)

[Handwritten mark]