

90.42

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21458-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 35-25S-3E  
1686 feet from S Section Line, 4377 feet from E Section Line  
Lease Name: HUTCHENS Well #: 3 OWWO  
County: BUTLER Total Vertical Depth: 2782 feet

Operator License No.: 5446  
Op Name: GILES, BENJAMIN M.  
Address: 532 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	200		150 SX
PROD	4.5	2780		425 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC  
Proposal Rcvd. from: TOM SCHMIDT Company: \_\_\_\_\_ Phone: (316) 655-2411

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2009 2:10 PM KCC Agent: SHANE JONES

Actual Plugging Report:

12/16/09 BEN GILES CREW DROPPED SAND TO SAND TO BOTTOM TO 2690'.  
12/17/09 BEN GILES CREW CUTTING OFF SURFACE CASING HEAD. WE FOUND NO CEMENT AT SURFACE. 12/18/09 M&S WELL SERVICE RIGGED UP AND TAGGED SAND @ 2032'. THEY CAPPED IT WITH 4 SXS. THEY CAN'T GET CEMENT TO DO TOP PLUG TODAY. 12/21/2009 COPELAND OUT LOAD THE CASING AND PRESSURED UP TO 200 PSI. COPELAND PERFORATED @ 250' W/3.5' STRIPGUN LOADED AT 4 SHOTS PER FOOT. PERFORATING GUN AND COLLAR LOCATOR STUCK IN THE HOLE @ 250' COPELAND PARTED THE WIRE LINE. COPELAND TRIED CIRCULATING DOWN THE CASING AND CIRCULATED DRILLING MUD UP THE BACKSIDE. I SPOKE TO JEFF KLOCK ABOUT THE GUN STUCK IN THE HOLE. JEFF GAVE THE GO AHEAD TO DO THE TOP PLUG. COEPLAND CIRCULATED 80 SX OF 60/40 POS W/4% GEL DOWN THE CASING AND UP THE BACKSIDE. THEY FINISHED UP AT 2:10 PM. 12/22/2009 DAVE BOLLENBECK CHECKED TOP PLUG. FOUND IT APPROX 32' DOWN. TALKED TO TOM ABOUT CAPPING WELL WILL DO IT AFTER THE FIRST OF THE YEAR.

Perfs:

Top	Bot	Thru	Comments
2747	2764	CSG	
2744	2747	CSG	

2/25/10  
2010066791

RECEIVED  
DEC 29 2009  
KCC WICHITA

Remarks: CEMENT TK #34418

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

JK