

#120.22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20532-00-00
Spot: NESENW Sec/Twnshp/Rge: 17-12S-17W
3598 feet from S Section Line, 3012 feet from E Section Line
Lease Name: SCHMEIDLER A Well #: 6
County: ELLIS Total Vertical Depth: 3699 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210	0	w/150 sxs cmt
PROD	5.5	3693	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2010 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE HEIM Company: GRADY BOLDING CORPORATION Phone: (785) 623-2084

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
PC at 1407' w/unknown sxs cement.
Emergency plug with rig over the hole. Dakota break in.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2010 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Services RIH with tubing to 3400'.
Quality Cementing rigged to tubing - mixed and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix with 250# hulls mixed in.
Pulled tubing to 1850'. Quality rigged to tubing and pumped 170 sxs cement with 250# hulls mixed in to circulate cement to pit area.
Pulled tubing - rigged to 8 5/8" casing with a swedge - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Topped off 5 1/2" casing with 20 sxs cement. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3693	3696		Arbuckle
<p>2/25/10 2010060793</p> <p>RECEIVED KANSAS CORPORATION COMMISSION</p> <p>FEB 16 2010</p> <p>CONSERVATION DIVISION WICHITA, KS</p>			

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3734.

Plugged through: TBG

District: 04


Signed

Pat Staab
(TECHNICIAN)

CM

FEB 09 2010

ISERN-WELLS #6 SCHMEIDLER 'A' 17-12-17W
 ELLINWOOD, KS. NE SE NW
 Contr. LEBEN DRLG., INC. Cty. ELLIS
 Geol. WARREN JOHNSON Pool BEMIS-SHUTTS
 E. 2168 KB Cm. 11/13/69 Cp. 12/18/69 IP PMP 35 BOPD +10%
 API 15-051-20,532 WTR/ARB 3693-96



SMP Tops	Depth	Datum
ANH	1379	+ 789
TOP	3133	- 965
HFFB	3369	-1201
LANS	3419	-1251
SIMP SH	3668	-1500
ARB	3691	-1523
TD	3696	-1528
DDTD	3698½	-1530½

Csg. 8-5/8" 210/150 SX;
 5½" 3693/125 SX
 DST 3480-3515/1', 60' HOCM, BHP
 311-266#/30", FP 53-62#
 COTD, BAIL 12 BO ½ HR, 1 BBL AC
 SD/12 HRS, FU 475' OIL, SWB DN,
 A 250, NO PRESS, SWB BK LD
 (SHORT 16 BL) SQZ 50 SX, SD-
 CO & DD 3698½, NSN, A 250, FU
 1100' OIL/12 HRS, SWB 3½ BFPH/6
 HRS, 10% WTR, POP
 NO LOG
 NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS