

148.82

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01218-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 15-33S-11W
1649 feet from S Section Line, 4941 feet from E Section Line
Lease Name: PAGE A Well #: 3
County: BARBER Total Vertical Depth: 4579 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	228		WITH 150 SX CMT
PROD	5.5	4545	3000	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2010 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SPOT 75 SX CMT ON BOTTOOM THROUGH TBG. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2010 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SPOT 75 SX CLASS A CMT W/2% CC AT 4425'. TAG TOC @ 3680'. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4545	4579	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 29 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

DATE 2/25/10
INV. NO. 2010060802

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JAN 15 2010

KCC DODGE CITY

Form CP-173