

\$ 77.00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02802-00-00
Spot: SESESW Sec/Twnshp/Rge: 25-14S-14W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BEN REIN Well #: 13
County: RUSSELL Total Vertical Depth: 2390 feet

Operator License No.: 30317
Op Name: J.H. R., INC.
Address: 533 WASHINGTON RD STE 100
BRIDGEVILLE, PA 15017

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	518	0	w/unknown sxs cmt
PROD 7		2390	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2010 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: STEVE Company: J.H.R., INC. Phone: (412) 221-3102

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.
Perfs: 725' - 350'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2010 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 2349' - pumped 11 sxs gel - followed with 50 sxs cement with 100# hulls mixed in.
Pulled tubing to 725' - pumped 100 sxs cement with 150# hulls mixed in - cement circulated.
POOH. Hooked to casing and pumped 10 sxs cement.
Max. P.S.I. 500#.
Hooked to Braden head and pumped 5 sxs cement with 250# P.S.I.
Head leaked - cellar stayed full.

2/25/10
2010060805

RECEIVED
JAN 06 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3709.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

JAN 07 2010

SKELLY OIL COMPANY

#13 REIN

25-14-14W
SE SE SW 33

Contr. _____ RUSSELL _____ County

E 1735 RB Comm. _____ Comp. 1-23-53 IP 31 BOPD & 54 BW

Tops	Depth	Datum
IND CAVE	2243	- 508
TARK	2300	- 565
TD	2390	- 655

Casing
 10" 518
 7" 2390
 PERF 2354-58, 38 B0 &
 74 BWPD
 PB 2300: PERF 36/2263-
 69
 PERF 24/2243-47
 SANDFRAC
 HALL-GURNEY POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS