

#105.95

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-02629-00-00  
Spot: SWSWSESE Sec/Twnshp/Rge: 10-14S-14W  
132 feet from S Section Line, 1035 feet from E Section Line  
Lease Name: SAM BOXBERGER Well #: 13  
County: RUSSELL Total Vertical Depth: 3260 feet

Operator License No.: 30317  
Op Name: J.H. R., INC.  
Address: 533 WASHINGTON RD STE 100  
BRIDGEVILLE, PA 15017

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	831	0	w/unknown sxs cmt
PROD	7	3259	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2010 2:30 PM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: WARD CRAIG Company: J.H.R., INC. Phone: (785) 483-1543

Proposed Plugging Method:	Ordered 500 sxs 60/40 pozmix - 4% gel - 700# hulls. Perfs: 1600' - 850' - 150'. Junk in the well at 2660'.
---------------------------	------------------------------------------------------------------------------------------------------------------

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2010 4:15 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2550' - pumped 100 sxs cement - followed with 100 sxs cement with 300# hulls mixed in.  
Pulled tubing to 1500' - pumped 200 sxs cement with 300# hulls - cement circulated.  
POOH. Hooked to casing and pumped 20 sxs cement.  
Max. P.S.I. 350#. S.I.P. 300#.  
Hooked to Braden head and pumped 20 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 04 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3540.

Plugged through: TBG

INVOICED  
DATE 2/25/10  
INV NO 2010060805

District: 04

Signed Ray Dinkel  
(TECHNICIAN) CM

TEXAS COMPANY

J0-14-14W

#13 S BOXBERGER APP S2 SE SE

Contr. STICKLE DRLG RUSSELL County


E.1850RB Comm. 2-2-56 Comp. 3-16-56 TP 25 BOPD/REAG

Tops	Depth	Datum
TARK	2438	+588
TOP	2704	+854
HEEB	2934	+1084
LANS	2992	+1142
REAG	3249	+1399
TD	3260	+1410

Casing  
10" 831  
7" 3259

CO. 3260

HALL GURNEY



1035' WEST OF EL.  
132' NO OF SL OF SE/4

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS