

\$ 87.72

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05332-00-00
Spot: SWNENW Sec/Twnshp/Rge: 15-18S-1W
4249 feet from S Section Line, 3603 feet from E Section Line
Lease Name: SCHULZ Well #: 1
County: MCPHERSON Total Vertical Depth: 2699 feet

Operator License No.: 31822
Op Name: JOLEN OPERATING COMPANY
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	169		100 SX
PROD	5.5	2671	410	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2009 8:00 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/05/2010 12:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

12/28/2009 EXPRESS DROPPED SAND. WAS NOTIFIED THAT HAD UNSCREWED FROM PACKER AND LEFT AN 8' SUB AND PACKER PUSHED TO BOTTOM. 12/29/2009 PERF TECH RAN IN W/BAILER AND 2 SXS CEMENT. THEY TAGGED A BRIDGE AT 2650', BUT COULD NOT FILL ANY PICK UP. THEY WENT DOWN TO 2690' WHERE THEY HAD A SOLID PICK UP. THIS PUT THEM INTO THE OPEN HOLE. JOLEN DECIDED TO RUN TUBING INTO 2600' AND SPOT A 35 SXS PLUG USED 60/40 POS 4% GEL 1.5% CAC1. TK #23890 EXPRESS THEN PULLED THE TUBING, AND PERF TECH RAN DOWN AND TAGGED CEMENT @ 2560'. EXPRESS THEN TIED ON TO THE CASING AND PULLED STRETCH. CASING PARTED WHERE FLANGE FOR SURFACE HEAD HAD BEEN WELDED ON. JOLEN HAD SHULZ WELDING COME OUT AND WELD ON A COLLAR. EXPRESS THEN PULLED 1.25" OF STRETCH. PERF TECH TRIED SHOOTING OFF PIPE AT 540'. PIPE DID NOT COME FREE. SHUT DOWN FOR THE NIGHT. 12/30/09 PERF TECH SHOT OFF CASING @ 410' PULLED THE FIRST JOING (20') CONSOLIDATED THEN TIED ON AND SPOTTED 35 SXS 60/40 W/4% GEL AND 2% CAC1. CONSOLIDATED THEN CIRCULATED 190 SXS 60/40 POS W/4% GEL TO SURFACE. TK #23930. 12/31/2009 I CHECKED TOP PLUG DROPPED STRING LINE 150' PLUS AND DID NOT TAG. I NOTIFIED PERRY ABOUT TOP PLUG HAD FALLEN. I ASKED HIM TO RUN ALINE DOWN AND TAG PLUG. IF IT HAS FALLEN BELOW SURFACE MAY HAVE TO RUN BACK IN WITH TUBING. 1/5/2010 CLASSIC WELL SERVICE RIGGED UP AND RAN TUBING TO APPROX 390' TAGGED CEMENT. THEY PULLED BACK UP TO THE FIRST FULL JOINT, AND CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE. CLASSIC PULLED TUBING AND CONSOLIDATED TOPPED OFF THE WELL. TK #23931 WITH 155 SXS 60/40 POS W/4% GEL AND HULLS. 1/7/10 GREG EVES CHECK TOP PLUG, CEMENT AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
2671	2699	OH	


RECEIVED
JAN 14 2010
KCC WICHITA

2/25/10
2010060806

Remarks:

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

1/4