

\$112.61

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25361-00-00  
Spot: W2SWNE Sec/Twnshp/Rge: 12-17S-15W  
1980 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: D. PIZINGER Well #: 1  
County: BARTON Total Vertical Depth: 3465 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	603		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2009 8:00 PM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: DAVID WILSON Company: KAHAN AND ASSOCIATES, INC. Phone: (918) 492-9797

Proposed Plugging Method: Ordered 165 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE  
Date/Time Plugging Completed: 12/19/2009 10:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 953' w/40 sxs.  
2nd. Plug at 553' w/70 sxs.  
3rd. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
DEC 28 2009  
KCC WICHITA  
INVOICED  
DATE 2/25/10  
INV. NO. 2010060807

District: 04

Signed Ray A Dinkel  
(TECHNICIAN) CM

DEC 21 2009