

\$ 77.48

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19114-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 26-17S-4E
4205 feet from S Section Line, 2322 feet from E Section Line
Lease Name: HAEFNER Well #: 1
County: MARION Total Vertical Depth: 2384 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		150 SX
PROD	4.5	2370	896	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2009 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 07/27/2009 10:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:
7/09 KELSOS PULLED TUBING AND RODS, SANDED OFF BOTTOM TO 2290' & CAPPED W/5 SXS CEMENT. SHOT OFF CASING AT 896' AND PULLED CASING.
7/27/2009 COPELAND CEMETN DOING TOP PLUG. RAN 1.25" POLY SPOOL IN THE HOLE TO 260'. THEY PUMPED 150 SXS OF 60/40 POS W/4% GEL AND NEVER GET IT TO CIRCULATE TO SURFACE. FLUID GOT WITHIN APPROX 45' OF SURFACE, BUT AS SOON AS STOPPED PUMPING FLUID FELL OUT OF SITE. COPELAND CALLED MIKE KELSO. MIKE SAID TO LET IT SET AND WOULD COME BACK AND TAG PLUG ON WEDNESDAY AND GO FROM THERE. THEY PULLED THE POLY BACK OUT OF THE HOLE, AND SHUT DOWN FOR THE DAY. 7/28/09 CHECKED TOP PLUG 100' DOWN TO PLUG AND FOUND LUID @ 99'. 7/29/09 COPELAND BACK OUT TOPPING OF WELLS WITH POLY LINE. 7/30/09 CHECKED CEMENT. CEMENT @ SURFACE TOPPPED OFF WITH 60 SXS TK #33038.

Perfs:
INVOICED
DATE 2/25/10
INV. NO. 2010060809

RECEIVED
DEC 29 2009
KCC WICHITA

Remarks: GPS: LAT: 38.54842, LONG: 96.95640
Plugged through: TBG

District: 02 Signed [Signature] (TECHNICIAN)

[Handwritten mark]