

\$185.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20814-00-00
Spot: NENE Sec/Twnshp/Rge: 36-31S-41W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: DUNN Well #: 36-1
County: MORTON Total Vertical Depth: 5700 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: PO BOX 1330 REGULATORY GROUP
HOUSTON, TX 77251

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 5270 | | WITH 20 SX CMT |
| SURF | 8.625 | 1584 | | WITH 900 SX CMT |
| DVT | | 2990 | | WITH 250 SX CMT |
| PROD | 5.5 | 5441 | 1638 | WITH 510 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2010 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 660' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2010 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMP 400# HULLS & 25 SX CMT AT 5000'. 2ND PLUG AT 1560' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5318 | 5322 | | |
| 4994 | 5000 | | |

INVOICED
DATE 2/25/10
INV. NO. 2010060810

RECEIVED
FEB 08 2010
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED

JAN 14 2010

KCC DODGE CITY

AWL