

\$156.62

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00613-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 8-30S-8W  
2640 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: RALL Well #: 1  
County: KINGMAN Total Vertical Depth: 4819 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	328		200 SX
PROD	5.5	4667	1240	400 SX

Well Type: SWD UIC Docket No: D07256.0 Date/Time to Plug: 03/05/2009 8:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: CHUCK TONER Company: PPSI Phone: (620) 546-4752

Proposed Plugging Method: CIBP 4000' & 2 SKS CMT, RECOVER PIPE FROM 1300' PULL FROM WELLBORE. RUN TUBING TO 1300' SPOT 35 SKS CMT. PULL TO 900' 35 SKS CMT. PULL TO 400' 35 SKS CMT. PULL TO 200' CIRC TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2009 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4000' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 1300' AND PULLED 1290', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', HOLE WOULDN'T LOAD WITH 40 BBLs OF WATER. SDFN. SPOTTED 50 SKS CMT AT 900' WAITED 2 HOURS FOUND CMT AT 850'. LOADED HOLE WITH DRILLING MUD. PULLED CASING TO 400' AND SPOTTED 35 SKS CMT, DISPLACED WITH MUD. PULLED CASING TO 240' AND CIRCD CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4667	4819		

INVOICED  
DATE 3/03/10  
INV NO. 2010060850

RECEIVED  
JAN 27 2010

Remarks: ALLIED CMT 60/40 4% AND COMMON

Plugged through: CSG

KCC WICHITA

District: 02

Signed

(TECHNICIAN)

✓