

\$ 167.34

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-19009-00-00
Spot: N2SESW Sec/Twnshp/Rge: 3-32S-41W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 15-3A
County: MORTON Total Vertical Depth: 5149 feet

Operator License No.: 32659
Op Name: PHOENIX PETROCORP, INC.
Address: 6401 S CUSTER RD, STE 130
MCKINNEY, TX 75070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2995		
SURF	8.625	1531		WITH 650 SX CMT
PROD	5.5	5149	0	WITH 260 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2007 12:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: TERRY Company: PHOENIX PETROCORP Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2007 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG CASING COLLAPSED @ 3550'. SET CIBP @ 2995'. TEST CASING & FOUND HOLES @ 1845'. PULLED TBG & PACKER TO 970' & PUMPED 150 SX CLASS C CMT. GOOD CIRCULATION UP THE ANNULUS. 2ND PLUG WAIT ON CMT 3 HOURS. PERFORATE 5 1/2" @ 600'. PUMPED 216 SX CLASS C CMT. LOST CIRCULATION. 3RD PLUG PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 91 CMT & 150# HULLS. SDON. 4TH PLUG TOP OFF 5 1/2" WITH 15 SX CMT. PUMPED ANOTHER 50 SX CMT DOWN ANNULUS.

Perfs:

Top	Bot	Thru	Comments
5058	5063		

INVOICED
DATE 3/03/10
INV. NO. 2010060851

RECEIVED
DEC 14 2009

Remarks: USED CLASS CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

KCC WICHITA

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
DEC - 3 2009
KCC DODGE CITY

Form CP 22