

#177.13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20152-00-00
Spot: E2NESE Sec/Twnshp/Rge: 32-29S-22W
1980 feet from S Section Line, 510 feet from E Section Line
Lease Name: EDMONSTON "B" Well #: 1
County: FORD Total Vertical Depth: 5450 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	309		WITH 225 SX CMT
PROD	4.5	5435	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/04/2010 10:45 AM
Plug Co. License No.: 5121 Plug Co. Name: MOBILE DRILLING COMPANY, INC.
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING Phone: (620) 793-2315

Proposed Plugging Method: THRU 2 3/8" TUBING OPEN-ENDED AT 5340 SPOT 25 SX CEMENT MIXED W/ 100# OF HULLS. PULL TBG TO ANHYDRITE CIRCULATE CMT. PULL TBG. TOP OFF. THEN 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2010 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

OPEN HOLE COMPLETION. CASING LEAK @ 490' SQUEEZED WITH 175 SX CMT. PUMPED 75# HULLS, 25 SX CMT THROUGH TBG @ 5340'. PULL TBG TO 1500 & CIRCULATE CMT TO SURFACE WITH 100 SX CMT. PULL REMAINDER OF TBG & TOP OFF WITH 15 SX CMT. 8 5/8" X 4 1/2" ANNULUS WAS FULL.

INVOICED RECEIVED
DATE 3/03/10 JAN 11 2010
INV. NO 2010060852 KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JAN - 6 2010
KCC DODGE CITY

Form EP 4/3