

88.99

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21769-00-00
Spot: S2NENW Sec/Twnshp/Rge: 19-25S-4E
4327 feet from S Section Line, 3317 feet from E Section Line
Lease Name: MARTENS Well #: 2
County: BUTLER Total Vertical Depth: 2738 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	169		90 SX
PROD	4.5	2737	1290	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL COMPANY INC Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2009 6:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIRCULATED TBG @ 2289', CIRCULATED HOLE CLEAN & CONSOLIDATED MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3 % CC AND DISPLACED IN CASING. PULLED TBG @ 1448', CONSOLIDATED MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC AND DISPLACED IN CASING. LAYED DOWN TBG, AND LAYED DOWN 31 JTS (1290') 4-1/2" CASING. RIH W/TBG @ 260', CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED AND PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11-12-2009, 6:00 PM. CONSOLIDATED CEMENT TICKET #23128. 8-13-2009, TOPPED WELL OFF TO SURFACE W/35 SXS 60/40 POZMIX 4% GEL.

Perfs:

Top	Bot	Thru	Comments
2665	2679	CSG	

INVOICED
DATE 3/03/10
INV. NO. 2010060855

RECEIVED
DEC 29 2009
KCC WICHITA

Remarks: 4-1/2" CASING PARTED @ 1290'. GPS LAT: 37.86612, LONG: 97.03498

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

14